INDEX TO SHEETS

PLAN NO.

701-01

702-20

702-40

702-96

702-97

702-99

902-05

905-01

905-02

905-03

907-01

907-03

907-04

SHEET NO.

201

202

203

204

205

206-208

209

210-212

213

214

215-220

221-223

224-225

SHEET NO.

400-403

TITLE SHEET AND LAYOUT MAP TYPICAL SECTIONS AND DETAILS

CITY/PARISH STANDARD PLANS

FOR STORM DRAINAGE PIPE

WEIR INLET

STANDARD BEDDING BACKFILL DETAILS

CAST IRON GRATE INLET AND JUNCTION BOX

FRAMES, GRATES, AND COVERS FOR INLETS AND MANHOLES (3 SHEETS)

TEMPORARY TRAFFIC CONTROL, TYP. APPLICATIONS

TEMPORARY TRAFFIC CONTROL, TYP, APPLICATIONS

BEGIN STA. 100+00 TO STA. 103+51.06

C.P. No. 20-EN-HC-0025

SIDEWALK AND HANDICAP RAMPS (6 SHEETS)

5-FOOT CHAIN LINK FENCE ON STRUCTURE

TEMPORARY TRAFFIC CONTROL (3 SHEETS)

CAST-IN-PLACE DRAINAGE STRUCTURES

PRECAST DRAINAGE STRUCTURE

COMMERCIAL DRIVES (3 SHEETS)

RESIDENTIAL DRIVES (2 SHEETS)

CROSS SECTIONS

2-3 SUMMARY SHEET PLAN & PROFILE SHEETS

CITY OF BATON ROUGE AND PARISH OF EAST BATON ROUGE

DEPARTMENT OF TRANSPORTATION AND DRAINAGE ENGINEERING DIVISION

PLANS OF PROPOSED

GROUP PROJECT SIDEWALK IMPROVEMENTS

CENTURION AVENUE SIDEWALK O'NEAL LANE TO CROSSBOW DRIVE CITY PARISH PROJECT No. 20-EN-HC-0024

MULLEN DRIVE SIDEWALK PERKINS ROAD TO HONEY DRIVE CITY PARISH PROJECT No. 20-EN-HC-0025



LAYOUT MAP


TYPE OF CONSTRUCTION:


TOTAL NO. OF SHEETS: 35

PERVIOUS AND IMPERVIOUS PORTLAND CEMENT CONCRETE SIDEWALKS, DRIVEWAYS, DRAINAGE STRUCTURES, EARTHWORK, SIGN RELOCATION, AND RELATED WORK

THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, CITY OF BATON ROUGE AND PARISH OF EAST BATON ROUGE, LOUISIANA, LATEST EDITION, AS AMENDED BY THE PROJECT SPECIFICATIONS, SHALL GOVERN THIS PROJECT.

DATUM USED:
CENTURION AVE:
HORIZONTAL: N: 2162670753, E: 1031301,355
VERTICAL: 11.135M (NAVD88 (COMPUTED USING GEOID18)
REFERENCE BENCHMARKS: ITRF2014(EPOCH: 2020.69089) MULIEN DR.: HORIZONTAL: N: 206896.33C, E: 1025119.027 VERTICAL: 11,266(M)[NAVD88 (COMPUTED USING GEOID18)] REFERENCE BENCHMARKS: ITRF2014(EPOCH: 2020.6904)





VICINITY MAP

RECOMMENDED FOR APPROVAL

SUSHIL JAIN, P.E. DESIGN ENGINEER DATE: 06/09/2021

RECOMMENDED FOR APPROVAL

MOVEBR PROGRAM MANAGER DATE: 6-16-21

RECOMMENDED FOR APPROVAL

RECOMMENDED FOR APPROVAL

CHIEF DESIGN & CONSTRUCTION ENGINEER


DIRECTOR OF DEPARTMENT OF TRANSPORTATION & DRAINAGE,






ALWINGHED AL

sheet Number



TYPICAL SECTION OF 6'-0" SIDEWALK CENTURION AVE

SCALE: 1" = 5'
APPLIES: STA, 10+00 TO 15+45



NOTE: SIDEWALK CROSS SLOPE MAY BE INCREASED UP TO 2% MAX TO RESOLVE GRADE REQUIREMENTS.

TYPICAL SECTION OF 5'-0" SIDEWALK MULLEN DRIVE

> SCALE: 1" = 5" APPLIES: STA. 100+50 TO 103+50






JUNE 15, 2021

SHEET 2

MOYEBR



TRANSVERSE SECTION

TREE ROOT PROTECTION DETAILS SCALE: $\frac{1}{2}$ " = 1'-0"

NOTES:
1. DO NOT CUT ROOTS GREATER THAN 2" IN DIA.

- DO NOT CUT ROOTS GREATER THAN 2" IN DIA.

 IF ROOTS ARE 2" IN DIA. OR MORE TOP SHAVE TO A MAXIMUM OF % OF ITS DIAMETER.

 IF ROOT TOP SHAVING IS DONE MORE THAN % ITS DIAMETER, THE PROJECT ENGINEER HAS

 TO BE NOTIFIED FOR ANNUAL TREE INSPECTION FOR HEALTH AND STABILITY.

 IF ROOTS HAVE TO BE REMOVED AT THE CLOSER END OF SIDEWALK BEFORE CONCRETE

 REPLACEMENT, IT CAN ONLY BE DONE AT A MINIMUM DISTANCE OF 3 TIMES TREE TRUNK

 DIAMETER FROM ITS CENTER.

 MAXIMUM CHANGE IN GRADE FOR CREST OR SAG APPROACHES IS LIMITED TO 5%

 AROUND TREE PROTECTION SIDEWALKS.

 3" MAXIMUM EXCAVATION BELOW EXISTING GRADE.

 ALL WORK AND ITEMS ASSOCIATED WITH TREE ROOT PROTECTION DETAIL SHALL BE PAID

 FOR UNDER ITEM 9900004 TREE ROOT PROTECTION BY THE SQUARE YARD.

CENTURION AVE/MULLEN DR SIDEWALKS

CITY-PARISH PROJECT NOS. 20-EN-HC-0024 & 20-EN-HC-0025 SUMMARY OF ESTIMATED QUANTITIES

ITEM NO.	PAY ITEM	QUANTITY -	UNITS
1195312	TWELVE (12) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	204	LF
1195324	TWENTY-FOUR (24) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	40	LF
2010100	CLEARING AND GRUBBING	1	LUMP
2020100	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	1	LUMP
2020600	REMOVAL ON CONCRETE WALKS AND DRIVES	113	SY
2020700	REMOVAL OF CONCRETE CURBS	12	LF
2020900	SAW CUTTING CONCRETE OR ASPHALT	82	LF
2030800	EXCAVATION AND EMBANKMENT	1	LUMP
4010100	TRAFFIC MAINTENANCE AGGREGATE	9	CY
5101005	5" PERVIOUS CONCRETE PAVEMENT	1011	SY
7010218	18" REINFORCED CONCRETE PIPE	359	LF
7010224	24" REINFORCED CONCRETE PIPE	193	LF
7020308	GRATE INLET (CPS 702-08)	1	EA
7020502	WEIR INLET (CPS 702-23)	5	EA
9020105	5' CHAIN LINK FENCE	100	LF
9030800	SEED	330	LBS
9030900	FERTILIZER PROPERTY.	305	LBS
9031000	WATER (FOR SEEDING AND FERTILIZER)	0.4	MGAL
9050100	TEMPORARY SIGNS AND BARRICADES	1	LUMP
9070101	INTEGRAL CONCRETE CURB (MOUNTABLE)	12	LF
9070106	INTEGRAL CONCRETE CURB (6" BARRIER)	32	LF
9070304	4" CONCRETE WALKS	59	SY
9070406	6" CONCRETE DRIVES	108	SY
9090100	MOBILIZATION	1	LUMP
9900001	TRUNCATED DOME INSET	84	SF
9900002	RELOCATION OF EXISTING ROAD SIGN	3	ËΑ
9900003	CONORETE COLLAR	2	EA
9900004	TREE ROOT PROTECTION	9	SY
			WAY TO THE





		_				
	S NO	SHE'E JMB	T EJR		3	
	HSIEVE TOUND NOT BE HERE	LAST BATON NOOEL LANSH	ark on EN. UC constrain	20-LIA-110-002+823		
-	HSHER		ату	PROJECT	STATE	PROJECT
	DESIGNED H.A	CHECKED S.J	DETALED XXX	CHECKED XXX	DATE 06/09/21	SHET XXX
***						Э¥
		ļ ļ				NOL
						REVISION DESCRIPTION
					,	DATE
_			ļ			Ċ
-	$\overline{}$	_	P	1	-	_





GENERAL NOTES:

- 1) PRIOR TO BEGINNING ANY CONSTRUCTION, THE CONTRACTOR SHALL BE CHARGED WITH RESPONSIBILITY OF CONTACTING LA ONE CALL (1-800-272-3020), DOID FIBER, AND NON-PARTICIPATING UTILITY COMPANIES AND VERIFY THE EXACT LOCATION, DEPTH, OR HEIGHT OF ALL UNDERGROUND AND OVERHEAD UTILITIES, THE CONTRACTOR SHALL BE HELD SOLELY RESPONSIBLE FOR ANY DAMAGE OR LIABILITIES OCCASIONED BY HIS FAILURE TO COMPLY WITH THESE INSTRUCTIONS, MINIMUM SIDEWALK CLEARANCE AT UTILITY CONFLICTS SHALL NOT BE LESS THAN 36 INCHES FOR AREAS WHERE UTILITIES CANNOT BE ADEQUATELY MOVED FROM THE SIDEWALK.
- 2) UTILITY COMPANIES SHALL BE RESPONSIBLE FOR THE ADJUSTMENT OF THEIR INDIVIDUAL ITEM (UTILITY POLES, GUY WIRES, FIRE HYDRANTS, WATER, ETC.) AND REMOVE THEM FROM THE SIDEWALK AREA. THE CONTRACTOR SHALL BE RESPONSIBLE TO COORDINATE HIS WORK WITH THE VARIOUS UTILITY COMPANIES TO MEET THESE REQUIREMENTS.
- 3) THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REGULATION OF ALL TRAFFIC DURING CONSTRUCTION AND SHALL COMPLY WITH ALL REGULATIONS TO ENSURE THE SAFETY FOR THE WORKMEN AND THE PUBLIC DURING ALL PHASES OF CONSTRUCTION.
- 4) ALL TRAFFIC REGULATORY SIGNS SHALL ONLY BE REMOVED BY THE CITY-PARISH TRAFFIC ENGINEERING DIVISION. THE PLACEMENT OF NEW SIGNS OR THE RELOCATION OF EXISTING SIGNS SHALL BE DETERMINED AND APPROVED BY THE PROJECT ENGINEER.
- 5) ALL TREES, SHRUBS, PLANTS, ETC. LOCATED WITHIN THE SIDEWALK CONSTRUCTION AREA SHALL BE REMOVED BY THE CONTRACTOR UNLESS OTHERMISE NOTED, HOWEVER, PRIOR TO COMMENCING THE CLEARING WORK, THE CONTRACTOR SHALL NOTIFY THE AFFECTED PROPERTY OWNERS AT LEAST 14 DAYS IN ADVANCE TO ALLOW THEM THE OPPORTUNITY TO REMOVE AND SALVAGE THEIR PLANTS.
- 6) ALL PLANTS REQUIRED TO BE TRIMMED SHALL BE TRIMMED IN ACCORDANCE WITH STANDARD HORTICULTURAL OR ARBORICULTURAL PRACTICES, IN SOME CASES THE ENTIRE PLANT MAY HAVE TO BE REMOVED. IN THE AFOREMENTIONED CASE THE CONTRACTOR SHALL NOTIFY THE OWNER AND ALLOW THE OWNER TIME TO REMOVE THE PLANT THEMSELVES OR AS OTHERWISE STATED ON THE PLANS.
- 7) CONTRACTOR SHALL INSTALL, EXPANSION JOINTS AS PER D.P.W STANDARD.
- 8) CONTRACTOR SHALL PROVIDE TRANSVERSE (DUMMY) JOINTS AS PER D.P.W STANDARDS. CONTRACTOR SHALL PROVIDE CENTERLINE JOINTS IN DRIVEWAYS WHEN DRIVEWAYS EXCEED 18 FEET WIDE AT THE RIGHT OF WAY LINE.
- 9) THE CONTRACTOR SHALL BACKFILL AND COMPACT ALL EMPTY POST HOLES IMMEDIATELY UPON REMOVING A POST USING EXCAVATION FROM SIDEWALK AREA.
- 10) SIDEWALK SHALL BE PLACED SO AS NOT TO OBSTRUCT DRAINAGE FROM PROPERTIES TO DRAINAGE DITCH OR CATCH BASINS,
- 11) CONTRACTOR SHALL ENSURE THAT ALL VEHICLES USED ON THIS PROJECT FOR TRANSPORTATION OF MATERIALS ARE UNDER THE MAXIMUM ALLOWABLE LOADING FOR ROADS AND BRIDGES USED TO ACCESS THIS PROJECT.
- 12) CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING DRAINAGE THROUGHOUT THE ENTIRE CONTRACT, CONTRACTOR SHALL NOT BE ALLOWED TO IMPEDE THE DRAINAGE OF ANY AREAS OR CAUSE ANY OBSTRUCTIONS TO ANY WATER COURSES DURING CONSTRUCTION.
- 13) CONTRACTOR SHALL RE-GRADE ALL AREAS ALTERED BY CONSTRUCTION ACTIVITIES TO PROVIDE POSITIVE DRAINAGE. ALL WORK SHALL BE IN A MANNER ACCEPTABLE TO THE OWNER. IF CONTRACTOR DETERMINES THAT ANY AREAS AFFECTED BY CONSTRUCTION ACTIVITIES CANNOT BE RE-GRADED TO DRAIN, CONTRACTOR SHALL DOCUMENT (I.E. TAKE ELEVATION, PICTURES, ETC.) OF EXISTING CONDITIONS AND INFORM ENGINEER PRIOR TO CONSTRUCTION.
- 14) ALL VEHICLE/EQUIPMENT FUELING, WASHING AND MAINTENANCE SHALL BE PERFORMED OFF-SITE.
- 15) BEFORE DRAINAGE PIPE LAYING, THE CONTRACTOR SHOULD VERIFY EXISTING DRAINAGE PIPES ELEVATIONS AT BEGIN AND END TO MAKE SURE THEY ARE MATCHING WITH PROPOSED DRAINAGE PLAN.
- 16) CONTRACTOR SHALL IMPLEMENT SPILL PREVENTION AND CONTROL PROCEDURES.
- 17) SPRAYING OF POTABLE WATER SHALL BE IMPLEMENTED FOR DUST CONTROL ONCE THE SITE GRADING HAS BEGUN AND DURING WINDY CONDITIONS.
- 18) AFTER THE SITE IS STABILIZED, ANY SEDIMENT THAT HAS ACCUMULATED SHALL BE REMOVED AND HAULED OFF-SITE FOR DISPOSAL. CONSTRUCTION DEBRIS, TRASH, SILT FENCES, SANITARY TOILETS, ETC: SHALL BE REMOVED FROM THE SITE.

COMPANY	CONTACT PERSON	PHONE NUMBER	FAX NUMBER
AT&T	TRACY LAUVRAY	225-367-0613	N/A
BATON ROUGE WATER COMPANY	RYAN SCARDINA	225-928-1000, EXT. 7617	225-231-0339
COX COMMUNICATIONS	THOMAS FLOYD	225-806-4745	N/A
ENTERGY ELECTRIC DISTRIBUTION	JERRY KENNEDY	225-354-3060	225-354-3039
entergy - gas	MR. RICKY WATTS	225-354-3204	225-354-3039
DOTD DISTRICT 61	RENO JOHNSON	225-231-4129	225-231-4108
DOTD HEADQUARTERS	MELVIN BUECHE	225-379-1509	225-379-1853
UNIT] FIBER	BRYAN KUSTENMACHER	5044705190	N/A
DEMCO	JEFF BELLINGTON	225-262-3095	N/A
ENTERGY ELECTRIC TRANSMISSION	ALLISON GASPARD	225-754-6117	N/A
KMC TELCOM	TERRY ROSS	225-214-1150	225-757-8900
ATMOS ENERGY	DON MASON	225-622-2449 EXT. 209	N/A
U.S. SPRINT COMMUNICATIONS	MCCOY INGALLS	404-649-2340	N/A
WILLIAMS COMMUNICATIONS	RICHARD EVANS	918-573-5777	N/A
DOTD FIBER	ERIK SMITH	225-379-2520	N/A


COMPANY	ADDRESS	CONTACT PERSON	NUMBER
ARCHITECTURAL SERVICES	1100 LAUREL STREET, BATON ROUGE, LA 70802	MR. JIM FREY	225-389-4694
DESIGN DRAINAGE	1100 LAUREL STREET, BATON ROUGE, LA 70821	MR. TOM STEPHENS	225-389-3188
ENGINEERING	1100 LAUREL STREET, BATON ROUGE, LA 70821	MR. TOM STEPHENS	225-389-3188
FIELD ENGINEERING DIMISION	329 CHIPPEWA STREET, BATON ROUGE, LA 70805	MR. MIKE OLSON	225-389-3202
SEWER	1100 LAUREL STREET, BATON ROUGE, LA 70821	MR. RICKEY BROUILLETTE	225-389-5623
SOUTH MAINTENANCE	2931 VALLEY STREET, BATON ROUGE, LA 70808	MR. KEITH ROBERSON	225-389-3250
TRAFFIC	329 CHIPPEWA STREET, BATON ROUGE, LA 70805	MR. INGOLF PARTENHEIMER	225-389-3248
WASTEWATER TREATMENT & DISPOSAL	2443 RIVERROAD, SOUTH, BATON ROUGE, LA 70802	MR. ADAM SMITH	225-389-3240
ARBORIST	1100 LAUREL STREET, BATON ROUGE, LA 70802	MR. GREG BIVIN	225-389-4694


ITTM NO	DESCRIPTION UNIT		QUANTITIES		
ITEM NO.			AS BID	AS BUILT	
	SUMMARY OF QUANTITIES FOR CENTURIS	ON AVE			
1195312	TWELVE (12) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	L.F.	113		
1195324	TWENTY-FOUR (24) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	L.F.	19		
2010100	CLEARING AND GRUBBING	LUMP SUM	0.5		
2020700	REMOVAL OF CONCRETE CURB	L.F.	12		
5101005	5" PERVIOUS CONCRETE WALK	57	706		
9020105	5' CHAIN LINK FENCE	L.F.	100		
9030800	SEED	LB	150		
9030900	FERTILIZER	LB	140		
9031000	WATER	MGAL.	0.2		
9050100	TEMPORARY SIGNS AND BARRICADES	LUMP	0,5		
9070101	INTEGRAL CONCRETE CURB (MOUNTABLE)	L.F.	12		
9070106	INTEGRAL CONCRETE CURB (6" BARRIER)	LF.	32		
9090100	MOBILIZATION	LUMP	0.5		
9900001	TRUNCATED DOME INLET	SQ FT	16	1	
9900002	RELOCATION OF EXISTING ROAD SIGN	EACH	3		
	SUMMARY OF QUANTITIES FOR MULL			т "	
1195312	TWELVE (12) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	LF	91		
1195324	TWENTY-FOUR (24) INCH WIDE THERMOPLASTIC REFLECTIVE STRIPING (125 MIL)	LF	21	 	
2010100	CLEARING AND GRUBBING	LUMP	0.5	-	
2020100	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	1		
2020600	REMOVING OF CONCRETE WALKS AND DRIVE	SY	113.4		
2020900	SAW CUTTING CONCRETE OR ASPHALT	LF	82		
2030800	EXCAVATION AND EMBANKMENT	LUMP	1		
4010100	TRAFFIC MAINTENANCE AGGREGATE	C.Y	9		
5101005	5" PERVIOUS CONCRETE PAYEMENT	SY	304.6		
7010218	18" REINFORCED CONCRETE PIPE	LF	359.0	ļ.	
7010224	24" REINFORCED CONCRETE PIPE	LF	193		
7020308	GRATE INLET (CPS 702-08)	EACH	1		
7020502	WEIR INLET (OPS 702-23)	EACH	5		
9030800	SEED	ъ	180		
9030900	FERTILIZER	LB	165		
9031000	WATER	MGAL	0.2	ļ	
9050100	TEMPORARY SIGNS & BARRICADES	LUMP	0.5	ļ <u> </u>	
9070304	4" CONCRETE WALK	SY	59		
9070406	6" CONCRETE DRIVE	SY	108,4		
9090100	MOBILIZATION	LUMP	0.5	ļ	
9900001	TRUNCATED DOMES	SQ FT	58		
9900003	CONCRETE COLLAR	EACH	2		
9900004	TREE ROOT PROTECTION	SY	9	I	












PROJECT NO. SHEET 20-EN-HC-0024&0025 201

RIGID PIPE


(REINFORCED CONCRETE)



PIPE UNDER OR WITHIN 5 FEET OF STREETS AND PAVED SURFACES. ${\rm SCALE:} \ 1/2"{=}1'{-}0"$


FLEXIBLE PIPE


(CORRUGATED METAL, POLYVINYL CHLORIDE, AND POLYETHYLENE)




PIPE UNDER OR WITHIN 5 FEET OF STREETS AND PAVED SURFACES. ${\rm SOALE:} \ 1/2''=1'-0''$

* BEDDING UNDER PIPE SHALL BE 6* UNLESS OTHERWISE SPECIFIED IN THE PLANS OR SPECIAL PROVISIONS.





TYPICAL BEDDING DETAIL FOR REINFORCED CONCRETE BOX CULVERT



GENERAL NOTES

ALL MATERIALS AND WORK SHALL CONFORM TO THE LATEST EDITION OF THE CITY OF BATON ROUGE AND PARISH OF EAST BATON ROUGE—"STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION",

LEGEND

- 1 BEDDING MATERIAL COMPACTED TO 95% STANDARD PROCTOR DENSITY. (NO DIRECT PAY).
- BACKFILL MATERIAL (QUALITY EXCAVATED OR SELECT MATERIAL OR SAND).

 COMPACTED TO A DENSITY AT LEAST EQUAL TO SURROUNDING UNDISTURBED SOIL. (NO DIRECT PAY).
- BACKFILL MATERIAL (BACKFILL SAND), COMPACTED TO 95% STANDARD PROCTOR DENSITY. (NO DIRECT PAY).
- BACKFILL MATERIAL (QUALITY EXCAVATED OR SELECT MATERIAL).
 COMPACTED TO A DENSITY AT LEAST EQUAL TO THE SURROUNDING UNDISTURBED SOIL. (NO DIRECT PAY).
- 5) 67 LIMESTONE W/ GEOTEXTILE FABRIC.

Libered PROFESS

PIPE BEDDING SCHEDULE

(RIGID PIPE)

PIPE SIZE	T1 (MIN.)
12"-30"	6 "
36"60"	12"
66"96"	18"

STANDARD PLAN NO. DATED SHEET NO 701-01 February 8, 2008 1 OF 1

STANDARD BEDDING AND BACKFILL
DETAILS FOR
STORM DRAINAGE CONDUIT


DEPARTMENT OF PUBLIC WORKS

CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE

DESIGNED DRAWN CHECKED APPROVED

ARE GESCRIPTION BY R. ELLIS G. VANNIGE R. ELLIS T. STEPHENS

701-01



HALF-SECTION HALF-SECTION IN PAVEMENT NOT IN PAVEMENT
SEE NOTE 7
B B = 0,+
TYPE 6 FRAME & COVER
TOP VIEW TYPE 6 SCALE: 3/4"=1'-0"

SECTION A-A

TYPE 3

SCALE: 3/4"=1'-0"

	HALF-SECTION IN PAVEMENT	HALF-SECTION NOT IN PAVEMENT			,	HALF-SECTI		LF-SECTION IN PAVEMENT
		2'-0" VARIES 91"	ļ				2'-	-0" VARIES
<u>a</u>	2'	-0"	4	SEE NOTE 3	<u>a</u>			
J. Commission of the commissio	2"	2"	VARIES					
The part of the same					\$ 	2	, , , , , , , , , , , , , , , , , , ,	2"/
	Jw	A IW				Ĭ₩.	A	_ _ Iw

SECTION B-B

TYPE 6

SCALE: 3/4*=1'-0*

SHEET

202

20-BN-HC-0024&0025

STANDARD PLAN No. DEC. 6, 2010 702-20

CAST IRON GRATE INLET AND JUNCTION BOX

ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS

CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
DESIGNED DRAWN CHECKED APPROVED


GLP GLP GLP T. STEPHENS


PIPE SIZE DIMENSION ROUND ARCH PIPE A * PIPE (ROUND EQUIV.) 15" 2'--10" 18" 2'-10" 24" 2'-10" 3'-5" 36" 4'-0" 42^H 4'-8" 5'-2" 54" 5'-9" 60" 48" 5'-4" 8,--8, 71--6* 60* 8'-10"

* INCREASE AS REQUIRED TO PROVIDE MINIMUM TOP WIDTH OF 4' SQUARE.


- 1. SEE STANDARD PLAN 702-99 FOR FRAME AND COVER DETAILS. TYPE 3 OR TYPE 6 FRAME AND COVER REQUIRED.
- 2. PRECAST CONCRETE STRUCTURES CONFORMING TO STANDARD PLAN 702-97 MAY BE FURNISHED.
- DIAGONAL REINFORCEMENT REQUIRED FOR PIPE LARGER THAN 36".
 BARS SHALL LAP TO A FULL LENGTH VERTICAL BAR W/18d LAP LENGTH.
- 4. DIMENSION A MAY BE VARIED FOR SKEWED PIPE,
- 5. SEE STANDARD PLAN 702-96 FOR THICKNESS, REINFORCING STEEL, AND OTHER STRUCTURAL DETAILS.
- 6. SEE STANDARD PLAN 702-98 FOR FOR CURB TRANSITION DETAILS.
- DIAGONAL REINFORCEMENT REQUIRED, USE SAME REBAR SIZE AS TOP REINFORCING, PLACE AS BOTTOM STEEL IF LOCATED IN PAVEMENT.

-- PLAN STATION CALL-OUT





STANDARD WALL DETAIL



BOTTOM SLAB DETAIL

AT 28 DAYS MINIMUM.

NOTE:

SCALE: N.T.S,

WALL DIMENSIONS

WALL HEIGHT (FT)	"Tw" WALL THICKNESS (IN)	VERT. REBAR SPACING (IN)
0'⊢4'	6,0"	12"
4'⊢8'	6,0"	9"
8'10'	7.0"	9*
10'-12'	7.0"	5 *
12'-16'	8.0*	5*
16'-20'	9,0"	*

BOTTOM SLAB DIMENSIONS

"T#" SLAB THICKNESS (IN)	"A" OR "B" MAXIMUM WIDTH OF OPENING INSIDE STRUCTURE (FT)	MAXIMUM DEPTH STRUCTURE (FT)	REBAR REQ'D
6.0"	4'	8'	#4
7,0"	6'	12'	# 5
8.0"	8,	16'	#5
9.0"	10'	20'	# 6

BOTTOM SLAB THICKNESS TO MEET MINIMUM CRITERIA SHOWN FOR OPENING WIDTH AND STRUCTURE DEPTH.

PAVEMENT SLAB DIMENSIONS

"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"TP" SLAB THICKNESS (IN)	REBAR REQ'D *	Intermediate Support Beam Req'd (Y or N)
≲10'	≤ 4'	7.0"	# 5	N
≤10'	4'6'	8.0"	# 5	N
≤10′	6'-8'	10.0"	#6	N
6'~8'	6'-8'	7.0"	#5	Y
8'-10'	8'-10'	8.0"	# 5	Y

★9" OC, EW, TB

LEDGE WIDTH MAY BE EXTENDED TO MAXIMUM WIDTH OF 1'-2" FOR SMALLER PIPE STRUCTURES TO SIMPLIFY CON-

STRUCTION FRAMING OF TOP SLAB.

REBAR MINIMUM LAP AND DEVELOPMENT LENGTHS

REBAR SIZE	LAP LENGTH (IN)	DEVELOPMENT LENGTH (IN)
#4	16*	12"
# 5	20*	16"
#6	24"	19"

SHOP DRAWING DETAILING REQ'D TO PROVIDE MINIMUM LENGTHS OR ELSE USE STANDARD HOOKS

#5 BAR A SCALE: N.T.S. 2 REQ'D PER FRAME 0.55 x PIPE DIAMETER

#5 BAR C

SCALE: N.T.S.

STEEL BAR ANCHOR


- TOP SLAB

REBAR

55%"

1 REQ'D PER PIPE ENTRANCE ≥ 36" Ø

53¾" #5 BAR B SCALE: N.T.S. 1 REQ'D PER FRAME



#3 BAR J SCALE: N.T.S. REQ'D STIRRUPS @ 4" OC

PROJECT NO.

20-BN-HC-0024&0025

ABBREVIATIONS: OC - ON CENTER

TB - TOP & BOTTOM

EW - EACH WAY

SHEET

#5 BAR D SCALE: N.T.S. 2 REQ'D PER EACH INTERMEDIATE BEAM

5. SLABS MAY BE PRECAST AND DOWELED INTO WALL SECTIONS. (SEE STD. PLAN 702-97) A=LENGTH INSIDE OPENING MEASURED PARALLEL TO CURB

4. SEE SHEET 702-99 FOR FRAME AND COVER DETAILS.

ALL REINFORCING STEEL TO BE DEFORMED GRADE 60 MINIMUM REBAR. STEEL BAR SIZE &
SPACING MAY BE ADJUSTED AS LONG AS AREA OF STEEL IS MAINTAINED PER FOOT.
 MINIMUM CONCRETE COVER FOR REBAR STEEL IS TO BE 3" FOR CONCRETE FACES CAST
AGAINST EARTH, 2.5" FOR FACES PERMANENTLY EXPOSED TO EARTH AND 2" FOR ALL OTHERS.

3, CONCRETE COMPRESSIVE STRENGTH FOR CAST-IN-PLACE STRUCTURES TO BE 4000 PSI

B-WIDTH INSIDE OPENING MEASURED PERPENDICULAR TO CURB TOD SI AD DIMENSIONS

TOP SEAD DIMENSIONS				
"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"T t" SLAB THICKNESS (IN)	* REBAR REQ ¹ D	
≤ 4′	≤ 4'	6.0"	#4	
4'-6'	4'6'	6,0"	# 5	
6'-8'	6'8'	6′0,	∦ 6	
8'-20'	8'-10'	7.0"	#6	

*9" OC, EW, SET 2" CLR. FROM SLAB BOTTOM

MIDDLE SLAB UNDER PAVEMENT DIMENSIONS


"A" INSIDE LENGTH (FT)	"B" INSIDE MDTH (FT)	"TMP" SLAB THICKNESS (IN)	* REBAR REQ'D
≤ 20'	≤ 4'	7.0*	#4
≤20'	4'6'	7.0*	# 5
≤20′	6'-8'	8,5*	# 6
≤20'	8'-10'	10.0*	# 6

* 9" OC, EW, SET 2" CLR. FROM SLAB BOTTOM


MIDDLE SLAB OUTSIDE PAVEMENT DIMENSIONS

001000	. , , , , , , , , , , , , , , , , , , ,	L. (1 D 14 E	11010110
"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"TM" SLAB THICKNESS (IN)	* REBAR REQ'D
≤20'	≤ 4'	7.0"	#4
≤20'	4'-6'	7.0"	# 5
≤20'	6'-8'	7.0*	# 6
≤20'	8'10'	8.0"	# 6


* 9" OC, EW, SET 2" CLR. FROM SLAB BOTTOM




INTERMEDIATE SUPPORT BEAM FOR DOUBLE CURB INLET SCALE: N.T.S.




TOP SLAB




SECTION A-A TOP SLAB INTERMEDIATE SUPPORT BEAM FOR DOUBLE CURB INLET SCALE: N.T.S.



TYPE 1 FRAME SUPPORT DETAIL SCALE: N.T.S.



TYPICAL SUPPORT BEAM BETWEEN DOUBLE CURB INLETS SCALE: N.T.S.




TYPE 2 FRAME IN PAVEMENT

SUPPORT DETAIL


SCALE: N.T.S.

TYPE 3 FRAME IN PAVEMENT SUPPORT DETAIL SCALE: N.T.S.



IN BOTTOM SLAB BELOW PIPE OUTSIDE WALL, IF "TB" DOES NOT MEET MIN. THICKNESS REO'D FOR PIPE O.D., PROVIDE THICKENED EDGE WITH MIN. WIDTH OF 2xTw. REINFORCE AS REQID. FOR BASE SLAB.

DATE





STANDARD PLAN No. DEC. 6, 2010 702-96 1 OF 1 CAST-IN-PLACE

DRAINAGE STRUCTURES (STRUCTURAL DETAILS)

ENGINEERING DIVISION
DEPARTMENT OF PUBLIC WORKS
OF BATON ROUGE & PARISH OF EAST BATON ROUGE
PESIGNED DRAWN CHECKED APPROVED
GLP GLP GLP T, STEPHENS DESCRIPTION

SCALE: N.T.S.






PRECAST WALL DETAIL


SCALE: N.T.S.

REBARS AT EQUAL


IN TABLES

SPACING AS SHOWN





#4 HOOP SCALE: N.T.S.



A=LENGTH INSIDE OPENING MEASURED PARALLEL TO CURB B=WIDTH INSIDE OPENING MEASURED PERPENDICULAR TO CURB PRECAST TOP SLAB DIMENSIONS


CITEON	01 101	OE/10 Dil	MENTOIOI 1	···
"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"Tt" SLAB THICKNESS (IN)	* REBAR REQ'D	* REBAR SPACING
≤ 4 ¹	≤ 4'	4.0"	#4	12*
4'6'	4'-6'	4,0"	# 5	12*
6'-8'	6'~8'	5.0"	# 5	8*
8'~20'	8'-10'	5.5"	#5	6"

* AS SHOWN OC. EW, SET 1-1/4" CLR. FROM SLAB BOTTOM

PRECAST MIDDLE SLAB UNDER PAVEMENT DIMENSIONS

	"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"TMP" SLAB THICKNESS (IN)	* REBAR REQ'D	* REBAR SPACING
ſ	≤ 20'	≤ 4'	5.0"	# 4	12"
I	≤ 20'	4'-6'	6.0"	#5	12"
I	≤ 20'	6'8'	7.0"	#5	8*
ĺ	≤ 20'	8'-10'	8.5*	# 5	6 *

* AS SHOWN OC, EW, SET 1-1/4" CLR. FROM SLAB BOTTOM




TYPICAL COMPOSITE STRUCTURE

SCALE: N.T.S.

SEE SIZE SHOWN IN TABLE OPTIONAL RISER UNIT

DIMENSION VARIES

SCALE: N.T.S.



BASE UNIT

SCALE: N.T.S.

PRECAST MIDDLE SLAB OUTSIDE PAVEMENT DIMENSIONS

"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"TM" SLAB THICKNESS (IN)	* REBAR REQ'D	* REBAR SPACING
≤20'	≤ 4'	5.0*	#4	12"
≤20'	4'-6'	5.0*	# 5	12"
≤20′	6'~8'	6.0*	#5	8"
≤20′	8'10'	6.5	# 5	6"

* AS SHOWN OC, EW, SET 1-1/4" CLR. FROM SLAB BOTTOM

PRECAST BOTTOM SLAB DIMENSIONS

"T#" SLAB THICKNESS (IN)	"A" OR "B" MAXIMUM WIDTH OF OPENING INSIDE STRUCTURE (FT)	MAXIMUM DEPTH STRUCTURE (FT)	REBAR REQ'D	REBAR SPACING
4.0"	4'	4'	#4	121
5.0*	6'	8'	# 5	12*
6.0"	8'	12'	# 5	12*
7.0"	8'	16'	# 5	12*
7.5	10'	20'	≱ 5	6

BOTTOM SLAB THICKNESS TO MEET MINIMUM CRITERIA SHOWN FOR OPENING WIDTH AND STRUCTURE DEPTH,

PRECAST PAVEMENT SLAB DIMENSIONS

	_ +				
INTERMEDIATE SUPPORT BEAM REQ'D (Y OR N)	"A" INSIDE LENGTH (FT)	"B" INSIDE WIDTH (FT)	"Tp" SLAB THICKNESS (IN)	REBAR REQ'D *	REBAR SPACING
N	≤10'	≤ 4'	6.0	# 5	12*
N	≤10'	4'6'	7.0"	# 5	12"
N	≤ 10'	6'8'	9.0"	#5	8"
Y	6'-10'	6'-10'	6.0"	# 5	12"

* AS SHOWN OC, EW, TB

PRECAST WALL DIMENSIONS

PROJECT NO.

WALL	"Tw"	VERT.
HEIGHT	WALL THICKNESS	REBAR SPAÇING
(FT)	(IN)	(IN)
0'-4"	4,0"	12"
4'-8'	5,0"	12"
8'10'	6.0 ^H	9"
10'-12'	6.0*	6"
12'-16'	7.0	4,5*
16'~20'	7.5 ^m	4.5*

NOTE:

- 1. THESE PRECAST UNITS ARE INTENDED TO BE USED AS THE LOWER PORTION OF A COMPOSITE STRUCTURE. STRUCTURAL AND FINISHING DETAILS ARE SHOWN ON OTHER STANDARD PLANS FOR STRUCTURE TYPES.

 2. ALL REINFORCING STEEL TO BE DEFORMED GRADE 60 MINIMUM REBAR. STEEL
- BAR SIZE & SPACING MAY BE ADJUSTED AS LONG AS AREA OF STEEL IS MAINTAINED PER FOOT IN ACCORDANCE WITH ASTM C913-08.
- 3. MINIMUM CONCRETE COVER FOR REBAR STEEL IS TO BE 1" FOR PRECAST CONCRETE WALLS AND 1-1/4" FOR OTHER PRECAST MEMBERS.
- CONCRETE COMPRESSIVE STRENGTH FOR PRECAST STRUCTURES TO BE 5000 PSI AT 28 DAYS MINIMUM. CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI BEFORE SHIPPING UNITS.
- SEE SHEET 702-99 FOR FRAME AND COVER DETAILS. SEE SHEET 702-96 FOR CAST-IN-PLACE STRUCTURAL DETAILS.
- PIPE OPENING TO BE FORMED ONLY WHEN REQUIRED.
- PIPE OPENING TO BE O.D. OF PIPE + 4"± 1/2".
- ALL PIPE ENDS TO BE SET FLUSH WITH INTERIOR WALLS FACE, PIPE ANNULAR SPACE IS TO BE GROUTED WITH NON-SHRINK GROUT AFTER INSTALLATION, GROUT AS REQUIRED TO CREATE INVERTS.
- 10. JOINTS BETWEEN PRECAST UNITS TO BE SEALED WITH FLEXIBLE PLASTIC GASKET MATERIAL AND WRAPPED WITH A 12" WIDTH OF GEOTEXTILE FABRIC. 11. JOINTS BETWEEN CAST-IN-PLACE SECTIONS AND OR PRECAST UNITS TO BE
- TONGUE AND GROOVE AND SEALED WITH TYPE II GRADE A EPOXY OR FLAT JOINT WITH A MINIMUM OF 12" OF No. 4 BARS AT 18" CTRS. (MAX.) 12, PRECAST CONCRETE INLETS CONFORMING TO STANDARD PLANS MAY BE
- FURNISHED, LEDGE WIDTH MAY BE REDUCED BY 1" AROUND INLET FRAMES TO 2-1/2". SUPPORT BEAM BETWEEN DOUBLE RETICULINE GRATE INLETS MAY BE REDUCED BY 2" DEPTH TO FORM 10"x10" BEAM.


- 13. PRECAST UNITS SHALL CONFORM TO SECTION 1017 OF THE STANDARD
- SPECIFICATIONS,
- 14. ALL PRECAST UNITS TO BE EQUIPPED WITH AT LEAST 2 COMMERCIALLY MANUFACTURED EMBEDDED INSERTS RATED FOR THE STRUCTURE'S LIFT LOAD IN COMPLIANCE WITH APPLICABLE ANSI AND OSHA STANDARDS (MINIMUM SAFETY FACTOR OF 4). EMBEDDED INSERTS TO CONSTRUCTED OF GALVANIZED SAFEL OR CORROSION RESISTANT MATERIALS AND INSTALLED BY PRECAST MANUFACTURER IN ACCORDANCE WITH SUPPLIERS INSTRUCTIONS, NO LIFT INSERTS SHALL REMAIN EXPOSED ON VISIBLE SURFACES AFTER THE STRUCTURE IS INSTALLED. NO LIFTING WITH CHAINS WRAPPED AROUND
- 15. PRECASTERS ARE REQUIRED TO BE NPCA CERTIFIED.
- 16. INSTALLATION OF PRECAST STRUCTURES ARE TO BE PER MANUFACTURER'S INSTRUCTIONS. ANY MODIFICATIONS TO STRUCTURES IN FIELD SHALL REQUIRE PRECASTER'S WRITTEN APPROVAL
- 17. MINIMUM THICKNESS OF STRUCTURAL ELEMENTS INSTALLED IN OR UNDER PAVEMENT SHALL BE 6".





STANDARD PLAN No.	DATED	SHT, No.
702-97	DEC. 6, 2010	1 OF 1


PRECAST DRAINAGE STRUCTURE (STRUCTURAL DETAILS)

DEPARTMENT OF PUBLIC WORKS BATON ROUGE & PARISH OF EAST BATON ROUG CHECKED APPROVED









GENERAL PROVISIONS

- All Temporary Traffic Control (TTC) Devices used shall be in accordance with the City Parish Standard Specifications for Public Works Construction, the current edition of the Manual on Uniform Traffic Control Devices (MUTCD), and the requirements of the National Cooperative Highway Research Program (NCHRP) 350 for Test Level 3. The MUTCD is available at http://mutcd.fnwa.dot.gov/
- The Contractor shall provide one or more authorized Traffic Control Supervisor (TCS) in accordance with the Standard Specifications.
- Materials used for Temporary Traffic Controls shall be in accordance with the City-Parish Standard Specifications for Public Works Construction and when applicable the City-Parish Qualified Products List (C-P QPL).
- No temporary traffic controls shall be erected without the approval of the City-Parish Traffic Engineer and until work is about to begin, unless they are covered
- No lane closures, lane shifts, diversions, or detours shall occur without the authorization of the City-Parish Traffic Engineer.
- Responsibility is hereby placed upon the contractor for the installation, maintenance, and operation of all temporary traffic control devices called for in these plans or required by the Project Engineer for the protection of the traveling public as well as all Department and construction personnel. All reflective devices such as signs, drums, barricades, vertical panels, delineators of any type, otc. shall be cleaned or washed periodically to maintain their effectiveness, as required by conditions or Project Engineer.
- The contractor shall also be responsible for the maintenance of all permanent signs and pavement markings left in place as essential to the safe movement and guidance of traffic within the project limits.
- The City-Parish Traffic Engineer shall serve as a technical advisor to the Project Engineer for all Traffic Control matters.
- 'Road Work XX Miles" sign shall be required on all projects and located at beginning of the project unless otherwise noted. The sign shall be a minimum 36"X60" unless otherwise noted.
- Warning signs used for lane closures or lane shifts in which the roadway shall be returned to full public use within 14 hours or less may be placed on NCHRP350 approved portable sign frames.
- The City-Parish will approve any detour route marking required to guide travelers around the construction area, but the contractor will be responsible for the required signage.

SPEED LIMITS

- Speed fimits shall be lowered by 10 mph for any construction, maintenance, or utility operation that requires one or more of the following: (A) the condition of the original highway is degraded due to milled surfaces or uneven pavements; (B) work is in progress in the immediate vicinity of the travel way requiring lone closures, ione width reductions, or low speed diversions; (C) workers present on the shoulder within 2' of the edge of traveled way without barrier protection.
- The reduced speed zone shall only apply to those portions of the project limits affected. The Project Engineer may allow SPEED LIMIT WHEN FLASHING signs to supplement reduced speed
 20065

- At the end of the reduced speed zone, a speed limit sign displaying the original speed limit before construction shall be installed.
- If conditions warrant, the City-Parish Traffic Engineer may authorize the reduction of the speed limit by more than 10 mph.

PAVEMENT MARKINGS (see C-P QPL)

- All pavement markings within the limits of the project that are in conflict with the project signing or the required traffic movements shall be removed from the pavement by blast cleaning or grinding (Existing striping shall not be painted over with black paint or covered with tape).
- If special pavement markings are needed, they shall be reflectorized, removable, and accompanied by the proper signage.
- Temporary Raised Pavement Markers (RPMs) may be added to supplement temporary striping in areas of transition, in tapers, in detours, and in other areas of need as directed by the Project Engineer.
- Materials and placement of temporary pavement markings shall conform to Section 905 of the Standard Specifications. If no pay item exists, temporary markings will be considered incidental to traffic control.


SIGNS


- All signs used for temporary traffic controls shall follow the Department's Standard Plans and the MUTCD. Signs shown in the Standard Plan illustrations are typical and may very with each specific condition.
- More appropriate signing for a specific condition may be required or substituted with the approval of the Project Engineer and reviewed by the City Parish Traffic Engineer.
- When projects are separated by less than one mile, they shall be signed as one project.
- At no time shall signs warning against a particular operation be left in place once the operation has been completed or where the obstacle has been removed.
- Signs over 10 sq ft shall be mounted on two post and signs over 20 sq ft shall be mounted on at least three post.
- . Signs shall have a minimum of two bolts per post.
- Permanent signs no longer applicable or in conflict shall be removed or covered with a strong, lightweight, opaque material.
- Warning signs used for temporary traffic controls shall meet the following guidelines unless otherwise noted in the plans: (A) size shall be 48' x 48', (B) see the Departments Standard Specifications and the C-P QPL for sheeting information, (C) a minimum of a 2 lb U-Channel post may be used driven to a minimum depth of 3', (D) sign height shall be a minimum of 5' above the roadway surface unless there is a concern for pedestrians or bicycle traffic in which it shall be a minimum of 7', (E) lateral distance of signs shall be a minimum of 6' from the edge of shoulder or edge of pavement if no shoulder exist and 2' from the back of curb in urban areas.
- Vinyl Roll Up signs will be allowed for short term (less than 12 hours) daytime work provided that they meet all size, color, retroreflectivity requirements, and NCHRP 350.
- Mesh rollup signs shall not be allowed on any project.

- All signs shall be removed or covered when no longer applicable.
- Contractor shall use caution not to damage existing signs which remain in place. Any signs damaged by work operations shall be replaced at the Contractor's expense.

CHANNELIZING DEVICES

- The following devices may be used: Tubular Markers, Vertical Panels, Cones, Drums, and Super Cones. Drums (at standard spacing) and Super Cones (at 1/2 standard spacing) are the only devices allowed to be used in taper areas on the interstate system during daylight hours. Only drums can be used in tapers during night
- Retroreflective material pattern used on super cones shall match that used on drums and conform to Section 1020-1.2(C) of the Standard Specifications.
- Specing of channelizing devices such as cones, panels, drums, and Type I or II barricades shall not exceed a distance in feet equal to the speed limit when used for taper channelization and a distance in feet of twice the speed limit when used for tangent channelization.
- 28" traffic cones are not allowed on: 1) Interstates, and 2) Highways with speeds greater than 40 mph.
- During night time operations: 1) 28" and 36" cones are not allowed, 2) drums are the only device allowed in the taper.








PROJECT NO. SHEET
20-EN-HC-0024&0025 210

BARRICADES

- Barricades shall be designed and applied in accordance with these standard plans and the current MUTCD guidance. Generally three types of barricades are used as below. Specific project applications shall be reviewed and approved by the City Parish Traffic Engineer and shall not deployed without such approval.
- Steady burn lights shall be used when barricades are used in a series for channelization.
- Type I barricades shall be used on low speed roads or urban streets.
- Type II barricades shall be used on high speed roads.
- Type III barricades shall be used to close a road section to traffic and shall extend completely across a roadway and its shoulders or from ourb to curb
- When signs and lights are to be mounted to a barricade, they must meet NCHRP 350 requirements.







- TYPE III BARRICADE **
- * Warning lights (optional)
- ** Rail stripe widths shall be 6 in, except that 4 in wide stripes may be used if rail lengths are less than 36 in. The sides of barricades facing traffic shall have retroreflective rail faces.



Day and Low-Speed

Readway ≤ 40 mph

8/6/10 DATE STANDARD PLAN NO. September 28, 2007 SHEET NO 1 OF 3

TEMPORARY TRAFFIC CONTROL

SEPTEMBER 28, 2007

ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS

CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE

COMPOSITION

DESCRIPTION

BY

MUTCO

G. CHENG

B. HARMON

I. PARTENHEIMER


REVISIONS

LIGHTING

- All temporary lighting shall be LED.
- Lighting shall supplement barricades that close one or more lanes or that
 extends across the roadway. A minimum of two lights will be used, but
 where a travel way ends immediately after a barricade, a minimum of four
 (4) lights shall be used. Lighting shall be by approved electrical
 installations. Battery operated equipment shall conform to NCHRP 350.
- High intensity flashing lights shall be used to mark the first advance warning sign.
- Low intensity flashing lights shall be used to mark all other hazards off the travel way.
- Steady burning lights shall be used on all traffic control devices used for channelizations.
- Flashing units will be mounted as high as possible and battery compartments shall be mounted 6" from the ground.


PORTABLE CHANGEABLE MESSAGE SIGNS.

- When working within the traveled way, including shoulders and auxiliary lanes. Changeable Message Signs (CMS) shall be used on all Interstate Highways and on all other roadways (where space is available) with an ADT greater than 20,000 and should be delineated with retroreflective TTC devices.
- When used in advance of a lane closure or a lane shift, the CMS should be placed on the right hand side of the road a minimum distance of 2 miles in advance of the taper for interstates and to be determined by the City-Parish Traffic Engineer on other roadways.
- CMS messages shall be approved by the City-Parish Traffic Engineer.
- When Portable Changeable Message signs are not being used, they should be removed; if not removed, they should be shielded by guardrail or barriers; or if the previous two options are not feasible, they should be delineated with retroreflective TTC devices.



FLAGGERS

- All flaggers must be qualified. The contractor shall be responsible for training or assuring that all flaggers are qualified to perform flagging duties. A certificate indicating completion of a flagger training course shall be available to the engineer if requested. A Qualified Flagger is one that has attended courses such as those offered by the American Traffic Safety Services Association (ATSSA) or other courses approved by the City-Parish.
- When utilized, a flagger shall use a minimum 18 inch sign on a minimum 6' stop/slow paddle and wear ANSI Class 2 vest during day time operations and ANSI Class 3 ensemble during night operations. In all flagging operations, the flagger must be visible from flagger advance warning sign.
- Flagger stations shall be in a highly visible location far enough in advance
 of the work site so that approaching traffic will have sufficient distance to
 reduce speed before entering the project. 200-300 feet is desirable. In
 urban areas, the advances distance may be decreased.



To STOP Traffic


Traffic Proceed

To Alert and Slow Traffic

USE OF HAND SIGN

FLASHING ARROW PANELS


- Flashing Arrow Panels shall be used for lane closures on all facilities with 2 or more tanes in a single direction and a speed limit greater than 35 mph.
- When used, flashing arrow panels should be located on the shoulder at the beginning of the taper.
- Where the shoulder width is limited, the flashing arrow panel should be placed within the closed lane as close to the beginning of the taper as practical.
- All Flashing Arrow Panels shall be 4' x 8' Type C with LED lighting.
- When Flashing Arrow Panels signs are not being used, they should be removed; if not removed, they should be shielded by guardrail or barriers or if the previous two options are not feasible, they should be delineated with retroreflective TTC devices.



PROJECT NO.	SHEET
20-EN-HC-0024&0025	211

ALLOWABLE LAP SPLICE FOR U-CHANNEL POST

 U-Channel posts may be spliced where long lengths are required. The upper section shall overlap the lower section by at least 24 inches. The bottom edge of the upper section of the splice shall be a minimum of 24 inches above the ground. The spliced sections shall be secured with at least four 5/16" inch diameter hexhead bolts spaced equally along the splice.



HIGHWAY-RAIL GRADE CROSSING

- When a highway-rail grade crossing exists within or upstream of the merging taper and it is anticipated that backups resulting from the lane closure might extend through the highway-rail grade crossing, the TTC zone should be extended so that the merging taper precedes the highway-rail grade crossing.
- When a highway-rail grade crossing exists within the activity area, provisions should be made to provide road users operating on the left side of the normal centerline with comparable warning devices as supplied for road users operating on the right side of the normal centerline.
- When a highway-rall grade crossing exists within the activity area, early coordination with the railroad company should occur before work starts.
- 4. When a highway-rall grade crossing exists within the activity area, a flagger may be used at the highway-rail grade crossing to minimize the probability that vehicles are stopped within 15 ft of the highway-rail grade crossing, measured from both sides of the outside rails.
- A truck-mounted attenuator may be used on the work vehicle and/or the shadow vehicle.



SEPTEMBER 28, 2007

STANDARD PLAN NO. DATED SHEET NO 2 OF 3

TEMPORARY TRAFFIC CONTROL

ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS

CITY OF BATON ROUSE & PARISH OF EAST BATON ROUSE

STANDARD PLAN NO. REVISION.

G. C. DESIGNED DRAWN CHECKED APPROVED

DESCRIPTION.

BY MUTCO G. CHENG B. HARMON I. PARTENHEIMER

PROJECT NO.	SHEET
20-BN-HC-0024&0025	212

Suggested Advance Warning Sign Spacing

	Dista	Distance Between Signs*		
Road Type	Α	В	С	
Urban (30 mph or less)	100	100	100	
Urban (35 mph or more)	350	350	350	
Rural	500	500	500	

* Distances are shown in feet. The column headings A, B, and C are the dimensions shown in Typical Application Figures. The A dimension is the distance from the transition or point of restriction to the first sign. The B dimension is the distance between the first and second signs. The C dimension is the distance between the second and third signs. (The third sign is the first one in a three-sign series encountered by a driver approaching a TTC zone.)

Formulas for Determining Taper Lengths

iulas for Determining Taper Lengths	
Speed Limit (S)	Taper Length (L) Feet
40 mph or less	$L = \frac{WS^2}{60}$
45 mph or more	L = WS

Where:

L = taper length in feet

W = width of offset in feet

S = posted speed limit in mph.

Meaning of Symbols on Typical Application Diagrams

Arrow panel

Arrow panel support or trailer (shown facing down)



Changeable message sign or support trailer



Channelizing device



Crash Cushion



Direction of temporary traffic detour



Direction of traffic



Flagger



High level warning device (Flag tree)



Luminaire



Pavement markings that should be removed for a long term project



Sign (shown facing left)



Surveyor



Temporary barrier



Temporary barrier with warning lights



Traffic or Pedestrian signal



Truck mounted attenuator



Type III Barricade



Warning lights



Work space



Work vehicle

Index to Typical Applications

Typical Application Description	Typical Application Number	Standard Plan Number
Work Outside of Shoulder		
Work Beyond the Shoulder	TA-1	905-02
Work on the Shoulder		
Work on Shoulders	TA-3	905-02
Shoulder Work with Minor Encroachment	TA-6	905-03
Work Within the Traveled Way of Two-Lane Highways		
Road Closed with Diversion	TA-7	905-03
Roads Closed with Off-Site Detour	8-AT	905-04
Lane Closure on Two-Lane Road Using Flaggers	TA-10	905-04
Lane Closure on Two-Lane Road with Low Traffic Volumes	TA-11	905-05
Temporary Road Closure	TA-13	<u>905</u> -05
Mobile Operations on Two-Lane Road	TA-17	905-06
Work Within the Traveled Way of Urban Streets		
Lane Closure on Minor Street	TA-18	905-06
Detour for One Travet Direction	TA-19	905-07
Detour for Closed Street	TA-20	905-07
Work Within the Traveled Way at an Intersection and Sid	ewaiks	
Multiple Lane Closures at Intersection	TA-25	905-08
Crosswalk Closures and Pedestrian Detours	TA-29	905-08
Work Within the Traveled Way of Multi-lane, Non-access	Controlled Highwa	iys
Interior Lane Closure on Multi-lane Street	TA-30	905-09
Half Road Closure on Multi-lane, High-Speed Highway	TA-32	905-09
Lane Closure on Divided Highway	TA-33	905-10
Work in the Vicinity of Highway-Rail Grade Crossings	•	
Work in Vicinity of Highway-Rail Grade Crossing	TA-46	905-10

Information contained herewith was taken directly from the MUTCD 2003 version.



SEPTEMBER 28, 2007

STANDARD PLAN NO. 905-01	DATED September 28, 2007	SHEET	Ŋ(
			_

TEMPORARY TRAFFIC CONTROL

ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS
CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
DESIGNED DRAWN CHECKED APPROVED
MUTCO G. CHENG B. HARMON I. PARTENHEIMER




Figure TA-1
Work Beyond the Shoulder

Notes:

- 1. If the work space is in the median of a divided highway, an advance warning sign should also be placed on the left side of the directional roadway.
- 2. The ROAD WORK AHEAD sign may be replaced with other appropriate signs such as the SHOULDER WORK sign. The SHOULDER WORK sign may be used for work adjacent to the shoulder.
- 3. For short-term, short-duration or mobile operation, all signs and channelizing devices may be eliminated if a vehicle with activated high-intensity rotating, flashing, oscillating, or strobe lights is used.
- 4. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.
- 5. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.





Figure TA-3 Work on Shoulders

ROAD WORK

NEXT X MILES

PROJECT NO. SHEET

20-EN-HC-0024&0025 213



The Workers symbol signs may be used instead of SHOULDER WORK signs.

 The SHOULDER WORK AHEAD sign on an intersecting roadway may be omitted where drivers emerging from that roadway will encounter another advance warning sign prior to this activity area.

 For short-duration operations of 60 minutes or less, all signs and channelizing devices may be eliminated if a vehicle with activated highintensity rotating, flashing, oscillating, or strobe lights is used.

lights is used.

5. Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.

6. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating flashing oscillating or strobe lights

rotating, flashing, oscillating, or strobe lights.

7. When paved shoulders having a width of 8 ft or more are closed, at least one advance warning sign shall be used. In addition, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

MOUT A PHIEDREMAN

SEPTEMBER 28, 2007

STANDARD PLAN NO. DATED SHEET NO. September 28, 2007 1 OF 1

TEMPORARY TRAFFIC CONTROL
TYPICAL APPLICATIONS

ENGINEERING DIVISION

DEPARTMENT OF PUBLIC WORKS
CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
6, C. DESIGNED DRAWN CHECKED APPROVED
BY MUTCO 0, CHENG B, HARMON I, PARTEDINEINER

This sheet shall be used with Standard Plan No. 905-01.




Figure TA-6 Shoulder Work with Minor Encroachment

Notes:

- All lanes should be a minimum of 10 ft in width as measured to the near face of the channelizing devices.
- The treatment shown should be used on a minor road having low speeds. For higher-speed traffic conditions, a lane closure should be used.
- For short-term use on low-volume, low-speed roadways with vehicular traffic that does not include longer and wider heavy commercial vehicles, a minimum lane width of 9 ft may be used.
- Where the opposite shoulder is suitable for carrying vehicular traffic and of adequate width, lanes may be shifted by use of closely spaced channelizing devices, provided that the minimum lane width of 10 ft is maintained.
- Additional advance warning may be appropriate, such as a ROAD NARROWS sign. Temporary traffic barriers may be used along the work space. The shadow vehicle may be omitted if a taper and channelizing devices are used.
- A truck-mounted attenuator may be used on the shadow vehicle. For short-duration work, the taper and channelizing devices may be omitted if a shadow vehicle with activated high-intensity rotating, flashing, oscillating, or strobe lights is used.
- Vehicle hazard warning signals may be used to supplement high-intensity rotating, flashing, oscillating, or strobe lights.
- 11. Vehicle hazard warning signals shall not be used instead of the vehicle's high-intensity rotating, flashing, oscillating, or strobe lights.

ROAD WORK Temporary payement Crash Cushlen ROAD CLOSED Temporary double Temporary pevement etarta here

PROJECT NO. SHEET 214 20-EN-HC-0024&0025

Figure TA-7 Road Closed with Diversion

Notes:

- Signs and object markers are shown for one direction of travel only.
- Devices similar to those depicted shall be placed for the opposite 2. direction of travel.
- Pavement markings no longer applicable shall be removed or obliterated as soon as practicable.
- Temporary barriers and end treatments shall be crashworthy.
- If the tangent distance along the temporary diversion is more than 600 ft, a Reverse Curve sign, left first, should be used instead of the Double Reverse Curve sign, and a second Reverse Curve sign, right first, should be placed in advance of the second reverse curve
- back to the original alignment.

 When the tangent section of the diversion is more than 600 ft, and the diversion has sharp curves with recommended speeds of 30 mph or less, Reverse Turn signs should be used.
- Where the temporary pavement and old pavement are different colors, the temporary pavement should start on the tangent of the existing pavement and end on the tangent of the existing pavement.
- Flashing warning lights and/or flags may be used to call attention to
- the warning signs.
 On sharp curves, large arrow signs may be used in addition to
- other advance warning signs. Delineators or channelizing devices may be used along the




SEPTEMBER 28, 2007


TEMPORARY TRAFFIC CONTROL TYPICAL APPLICATIONS

ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
DESIGNED DRAWN CHECKED APPROVED
MUTCO G. CHENG B. HARMON (. PARTENHEIMER

This sheet shall be used with Standard Plan No. 905-01.



Driveway Crossing w/ Walk Set Off Curb



General Notes

- 1. 1/2" expansion joints shall be placed using preformed joint filler at all junctions with existing concrete, adjacent to all curbs, manholes, and junction boxes, and around poles and similar obstructions.
- 2. 1/2" expansion joints shall be placed at no more than 100 foot spaces when long pours are not interrupted by driveways or junctions with other walks.
- 3. Dummy (crack control) joints shall be placed at intervals equaling the walkway width.
 - a. Impervious concrete walk joints may be tooled or sawn to a depth of 1/3 the concrete thickness. Sawn joints shall be cut between 24 and 48 hours after concrete placement.
 - b. Previous concrete walk joints shall be placed by rollers, pressed to form a joint depth of 1/3 the concrete thickness.
- 4. Where concrete walks pass through driveways the walks shall consist of impervious concrete of the same thickness as the driveway, but not less than 6 inches. The walk shall be formed on each side to provide a controlled cross slope. Dummy joints shall be tooled,
- 5. Curb ramps shall be installed as noted on the plans. Curb ramps and flares shall be built using impervious concrete unless noted otherwise.
- 6. Detectable wornings shall be provided at street intersections and bus stop loading areas and as otherwise noted on the plans. Detectable warnings shall also be provided at approaches to driveways that are STOP controlled by either signs or signals.


Referenced Standards

Refer to Std 907-03 for Commercial Driveways

Refer to Std 907-04 for Residential Driveways

Refer to Std 907-02 for Curb and Gutter Details






Section A

Note: Walkway Cross Slope May Be Increased to 2% max, to Resolve Grade Requirements,

Sidewalk Width -1/2" Exp. Jt. (Cont.) 1% See Note Note: Walkway Cross Slope May Be

Section B

Increased to 2% max. to Resolve Grade Requirements.



Note: Walkway Cross Slope May Be Increased to 2% max, to Resolve Grade Requirements,

Section C

NOTE: THIS DRAWING HAS BEEN PREPARED FOR USE ON PROJECTS INTENDED FOR CONSTRUCTION ON PUBLIC ROADS IN EAST BATON ROUGE PARISH, LA. OTHER USES ARE NOT AUTHORIZED.


BATON EAST

SHEET NUMBER 215


Standard Plan 907-01 Sidewalk and Handicap Ram (Typical Installations) Sheet 1 of 6





Department of portation & Drainage ngineering Division




7.5










STANDARD 5' SIDEWALK
WITH PAVED RAMP
TYPE 3
NTS




AREA OF CURB MODIFICATION

NOT

- LOCATION OF ALL TRAFFIC STRIPING, CROSS BARS, STOP BARS, AND MARKERS SHALL BE BASED ON SITE SPECIFIC DESIGN APPROVED BY THE CHIEF TRAFFIC ENGINEER. REFER TO 905-50 SHEET 7.
- 2. THE LAYOUT OF HANDICAP RAMPS ARE BASED ON USE OF 6 INCH BARRIER CURB. ADJUSTMENTS TO DIMENSIONS WILL BE REQUIRED SHOULD MOUNTABLE CURB IS USED.
- 3, RAMP CONFIGURATIONS MUST BE APPROVED BY THE CHIEF TRAFFIC ENGINEER.



NTS



STANDARD 5' SIDEWALK
WITH CURBED RAMP
TYPE (5)
(REFER TO NOTES, TYP.)
NTS



NOTE: THIS DRAWING HAS BEEN PREPARED FOR USE ON PROJECTS INTENDED FOR CONSTRUCTION ON PUBLIC ROADS IN EAST BATON ROUGE PARISH, LA. OTHER USES ARE NOT AUTHORIZED.





SHEET NUMBER


PANISSON EAST BATON ROUGE PARISH


CTT PROJECT STATE PROJECT

218









TYPE 9

EXIST. SIDEWALK -7

NOTE: REFER TO 907-02 FOR HAND!CAP RAMP CURB AND GUTTER

TYPE (12)


GRASS


1 24" DETECTABLE WARNING (NOTE 3)

RAMP WIDTH (4' MIN.) -

GRASS










AREAS OF CURB MODIFICATION

NOTE:


- LOCATION OF ALL TRAFFIC STRIPING, CROSS BARS, STOP BARS, AND MARKERS SHALL BE BASED ON SITE SPECIFIC DESIGN APPROVED BY THE CHIEF TRAFFIC ENGINEER. REFER TO 905-50 SHEET 7.
- 2. THE LAYOUT OF HANDICAP RAMPS ARE BASED ON USE OF 6 INCH BARRIER CURB, ADJUSTMENTS TO DIMENSIONS WILL BE REQUIRED SHOULD MOUNTABLE
- 3. THE MINIMUM LENGTH OF ANY SIDE OF THE DETECTABLE WARNING MATERIAL SHALL BE TWO FEET.





NOTE: YHIS DRAWING HAS BEEN PREPARED FOR USE ON PROJECTS INTENDED FOR CONSTRUCTION ON PUBLIC ROADS IN EAST BATON ROUGE PARISH, LA. OTHER USES ARE NOT AUTHORIZED.

SHEET 219









COMBINATION ISLAND RAMPS N.T.S.


AREAS OF CURB MODIFICATION

NOTES:

- 1. LOCATION OF ALL TRAFFIC STRIPING, CROSS BARS, STOP BARS, AND MARKERS SHALL BE BASED ON SITE SPECIFIC DESIGN APPROVED BY THE CHIEF TRAFFIC ENGINEER. REFER TO 905-50 SHEET 7.
- 2. THE LAYOUT OF HANDICAP RAMPS ARE BASED ON USE OF 6 INCH BARRIER CURB. ADJUSTMENTS TO DIMENSIONS WILL BE REQUIRED SHOULD MOUNTABLE CURB IS USED.
- NO SIGHT OBSTRUCTIONS SUCH AS BENCHES TREES, ETC. SHALL BE PLACED TO LIMIT THE REQUIRED SIGHT DISTANCE.
- 4. WHEN GEOMETRIC LIMITATIONS PREVENT CONSTRUCTION OF THE FLARED RAMP WITH AT LEAST 2 FEET OF FULL DEPTH CURB BETWEEN FLARES, USE CURBED RAMPS.
- 5. IF A PEDESTRIAN REFUGE IS REQUIRED OR DESIRABLE, A MINIMUM 6' LENGTH IS REQUIRED, AS WELL AS



NOTE: THIS DRAWING HAS BEEN PREPARED FOR USE ON PROJECTS INTENDED FOR CONSTRUCTION ON PUBLIC ROADS IN EAST BATON ROUGE PARISH, LA. OTHER USES ARE NOT AUTHORIZED.



(REFER TO NOTES, TYP.)
N.T.S.

NOTE: ALL SIDEWALK CURB RAMPS ON PUBLIC STREETS SHALL HAVE DETECTABLE WARNING SURFACES THAT EXTEND THE FULL WIDTH OF THE RAMP AND IN THE DIRECTION OF TRAVEL 24" FROM THE BACK OF THE CURB.

CURB RAMP DETECTABLE WARNING






SHEET NUMBER

ent of & Drainage · *Divisio*n

PROJECT NO. SHEET 20-EN-HC-0024&0025



COMMERCIAL DRIVE - TYPE 1 SINGLE NON-CURBED NO SIDEWALK N.T.S.

COMMERCIAL DRIVE - TYPE 2 SINGLE NON-CURBED WITH SIDEWALK ADJACENT TO CURB N.T.S.

EXISTING PROPERTY LINE PROJECTION — (REFER TO NOTE 8) REFER TO NOTE 1 SAWCUT PAVED DRIVE (FULL DEPTH) ⊢R/₩ (REFER TO P.C. CONC. DRIVE SIDEWALK TRANSITION (TYP.) NOTE 1) (REFER TO NOTE 11) (REFER TO NOTE 5) OF DI -NOTE 10 4" THICK S/W NOTE 4-/ NOTE 2 LIMITS OF DRIVEWAY 5'-0" CURB TRANSITION L5'-0" CURB TRANSITION (REFER TO SHEET 3-DETAIL 2 OR 4)

> COMMERCIAL DRIVE - TYPE 3 SINGLE NON-CURBED WITH OFFSET SIDEWALK N.T.S.

NOTES:

- 1. DRIVEWAY GEOMETRY SHOWN SHALL APPLY FOR BOTH NEW STREET CONSTRUCTION AND MODIFICATIONS TO EXISTING STREETS. R AND W -- REFER TO CONSTRUCTION PLAN FOR SPECIFIC DIMENSIONS WHEN PROVIDED, OTHERWISE
- 2. SIDEWALK THICKNESS SHALL MATCH DRIVEWAY THICKNESS AS SHOWN OR AS DIRECTED THE PROJECT ENGINEER.
- 3. CONSTRUCTION OR KEYWAY JOINT REQ'D WHEN DRIVE DIMENSIONS EXCEED 16' IN EITHER DIRECTION. LOCATION OF JOINTS SHALL BE COORDINATED WITH THE PROJECT
- 4. WITHIN THE DRIVEWAY LIMITS, SIDEWALK AREA SHALL HAVE SCORED JOINTS PER STANDARD PLANS AND SPECIFICATIONS. SIDEWALK EXPANSION AND CONSTRUCTION JOINT LOCATIONS SHALL BE PER 907-01.
- REFER TO STD. PLAN 907-01 FOR SIDEWALK RAMPS. SIDEWALK TRANSITION SHALL NOT EXCEED 1:12 SLOPE.
- MAXIMUM CHANGE IN GRADES IS 12% FOR A CREST AND 11% AT SAGS WITHOUT VERTICAL CURVES. MAXIMUM GRADE CHANGES SHOULD BE AT LEAST 10' APART. MAXIMUM GRADE TYPICALLY SHALL NOT EXCEED 20%.
- 7. REFER TO STD. PLAN 502-01 FOR CURB DETAILS AND STD. PLAN 907-C2 FOR COMBINATION CURB AND GUTTER DETAILS.
- 8. DRIVEWAY SHALL NOT EXTEND BEYOND THE ADJACENT PROPERTY LINE PROJECTION.
- 9. STREET TYPES ARE AS DEFINED BY THE TRAFFIC ENGINEER.
- 10. NEW SIDEWALKS SHALL BE TRANSITIONED TO MATCH THE EXISTING SIDEWALK AS DIRECTED BY THE PROJECT ENGINEER,
- 11. DRIVEWAY THICKNESS SHALL BE AS SHOWN ON THE CONSTRUCTION PLANS OR AS DIRECTED BY THE PROJECT ENGINEER, MINIMUM COMMERCIAL DRIVEWAY THICKNESS
- 12. REFER TO SHEET 3 FOR TYPICAL PROFILES AND DETAILS.



LEGEND

SIDEWALK AREA WITHIN DRIVEWAY (PAID AS DRIVEWAY) REFER TO NOTES 2 AND 4





DATED APRIL 16, 2009 SHEET NO.

COMMERCIAL DRIVES


GEOMETRIC DETAILS


ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
DESIGNED | DRAWN | CHECKED | APPROVED GLP GLP GLP T. STEPHENS 907-03












DRIVEWAY PLAN COLLECTOR AND ARTERIAL STREETS (REFER TO NOTE 10) N.T.S.



- DRIVEWAY GEOMETRY SHOWN SHALL APPLY FOR BOTH NEW STREET CONSTRUCTION AND MODIFICATIONS TO EXISTING
- SIDEWALK THICKNESS SHALL MATCH DRIVEWAY THICKNESS WITHIN LIMITS OF DRIVEWAY OR AS DIRECTED BY THE PROJECT ENGINEER.
- 3. CONSTRUCTION OR KEYWAY JOINT REQ'D WHEN DRIVE DIMENSIONS EXCEED 16' IN EITHER DIRECTION. LOCATION OF JOHN'S SHALL BE COORDINATED WITH THE PROJECT ENGINEER.
- 4. WITHIN THE DRIVEWAY LIMITS, SIDEWALK AREA SHALL HAVE SCORED JOINTS PER STANDARD PLANS AND SPECIFICATIONS. EXPANSION AND CONSTRUCTION JOINT LOCATIONS SHALL BE PER 907—01.
- 5. REFER TO STD. PLAN 907-01 FOR SIDEWALK RAMPS. SIDEWALK TRANSITION SHALL NOT EXCEED 1:12 SLOPE.
- 6. MAXIMUM CHANGE IN GRADES IS 12% FOR A CREST AND 11% AT SAGS WITHOUT VERTICAL CURVES. MAXIMUM GRADE CHANGES SHOULD BE AT LEAST 10' AFART. MAXIMUM GRADE TYPICALLY SHALL NOT EXCEED 20%.
- 7. REFER TO STD. PLAN 502-01 FOR CURB DETAILS AND REFER TO STD. PLAN 907-02 FOR COMBINATION CURB AND GUTTER DETAILS.
- 8. DRIVEWAY SHALL NOT EXTEND BEYOND THE ADJACENT PROPERTY LINE PROJECTION.
- 9. THE WIDTH OF THE DRIVEWAY AT THE THROAT SHALL BE A MINIMUM OF 12'.
- 10. STREET TYPES ARE AS DEFINED BY THE TRAFFIC ENGINEER.
- 11. NEW SIDEWALKS SHALL BE TRANSITIONED TO MATCH EXISTING SIDEWALKS AS DIRECTED BY THE PROJECT ENGINEER.
- 12. DRIVEWAY THICKNESS SHALL BE AS SHOWN ON THE CONSTRUCTION PLANS OR AS DIRECTED BY THE PROJECT ENGINEER. MINIMUM RESIDENTIAL DRIVE THICKNESS IS 6".

STANDARD PLAN NO. 907-04

LEGEND

SIDEWALK AREA WITHIN DRIVEWAY (PAID FOR AS DRIVEWAY) REFER TO NOTES 2 AND 4.



RESIDENTIAL DRIVES GEOMETRIC DETAILS

DATED APRIL 16, 2009

SHEET NO.

ENGINEERING DIVISION DEPARTMENT OF PUBLIC WORKS CITY OF BATON ROUGE & PARISH OF EAST BATON ROUGE
DESIGNED DRAWN CHECKED APPROVED
GLP GLP GLP T. STEPHENS

